

DELHI DEVELOPMENT AUTHORITY
दिल्ली विकास प्राधिकरण
Dwarka Sports Complex
द्वारका स्पोर्ट्स कॉम्प्लेक्स
Sector-11, Dwarka, New Delhi-110075
सेक्टर-11, द्वारका, नई दिल्ली-110075

No. F.14(21)DSC/DDA/C/2020-21/494
नंबर F.14 (21) डीएससी/डीडीए/सी/2020-21/494

Dated: 10/12/2020
दिनांक: 10/12/2020

Notice Inviting Quotation No.07/DSC/DDA/2020-21
एनआईक्यू नंबर 07/डीएससी/डीडीए/2020-21

Online quotations are invited on behalf of Delhi Development Authority, (Sports Wing) for the following works at Dwarka Sports Complex. The quotation shall be uploaded in two parts, namely, 'Part -I' containing Technical Bid and 'Part – II' comprising 'Financial Bid'. The bid not uploaded in accordance with the prescribed manner will not be accounted for at all. Only those agencies/ Firm/ Person have completed similar nature of work (Three or more similar nature works each costing not less than 40% of the estimated cost put to quotation, or two similar works costing each not less than 60% of the estimated cost put to quotation, or one similar works costing not less than 80% of estimated cost put to quotation) during the last seven years in Government Department or Public Sector undertaking with annual turnover more than 30% of the estimated cost in each year during the immediate last three consecutive financial year ending March 2019 duly certified by Chartered Accountant are entitled to apply. A proof thereof should be upload with the Technical Bid. The quotationer should be registered with the Department of GST and furnish a copy of registration with the quotation.

द्वारका स्पोर्ट्स कॉम्प्लेक्स में निम्नलिखित कार्यों के लिए दिल्ली विकास प्राधिकरण, (स्पोर्ट्स विंग) की ओर से ऑनलाइन कोटेशन आमंत्रित किए जाते हैं। कोटेशन को दो भागों में अपलोड किया जाएगा, अर्थात् भाग-1 जिसमें तकनीकी बोली और भाग - II शामिल हैं, जिसमें वित्तीय बोली शामिल है। निर्धारित तरीके से अपलोड नहीं की गई बोली का हिसाब बिल्कुल नहीं होगा। केवल उन एजेंसियों/फर्म/व्यक्ति ने समान कार्य की प्रकृति पूरी कर ली है (तीन या अधिक समान प्रकृति प्रत्येक कार्य करती है जिसकी लागत कोटेशन के लिए रखी गई अनुमानित लागत का ४०% से कम नहीं है, या दो इसी तरह के काम करता है अनुमानित लागत का ६०% से कम नहीं की लागत कोटेशन के लिए डाल दिया, या एक समान काम करता है अनुमानित लागत का ८०% से कम नहीं कोटेशन के लिए रखा) सरकारी विभाग या सार्वजनिक क्षेत्र के उपक्रम में पिछले सात वर्षों के दौरान वार्षिक कारोबार के साथ प्रत्येक वर्ष में अनुमानित लागत का 30% से अधिक मार्च २०१९ मार्च २०१९ को समाप्त होने वाले अंतिम वर्ष के दौरान प्रति वर्ष में 30% से अधिक चार्टर्ड एकाउंटेंट द्वारा विधिवत प्रमाणित लागू करने के हकदार हैं। इसका एक प्रमाण तकनीकी बोली के साथ अपलोड किया जाना चाहिए। कोटेशनर जीएसटी विभाग में पंजीकृत होकर कोटेशन के साथ पंजीकरण की प्रति प्रस्तुत करें।

Name of work: - Maintenance of Various Sports Complex/ Golf Courses (M/o DSC).

काम का नाम:-विभिन्न खेल परिसर/गोल्फ कोर्स (मेसर्स डीएससी) का रखरखाव।

SH: - Maintenance of old/damaged G.I pipe line, repair of broken RR masonry, repair of 02 nos. screen, plinth protection and other misc. work at Dwarka Sports Complex.

एसएच: - पुराने / क्षतिग्रस्त जी.आई पाइप लाइन का रखरखाव, टूटी हुई आरआर चिनाई की मरम्मत, 02 नग की मरम्मत। स्क्रीन, प्लिंथ प्रोटेक्शन और अन्य मैस्क। द्वारका स्पोर्ट्स कॉम्प्लेक्स में काम।

Estimated cost: Rs. 2,34,672/-

Earnest money-Rs. 10,000/-

अनुमानित लागत: रु। 2,34,672 / -

अग्रिम धन-10,000/-

(SCHEDULE OF QUANTITY ATTACHED)

गुणवत्ता की अनुसूची

Quotation documents can be obtained / download on the e-tendering portal i.e. *website <https://eprocure.gov.in/eprocure/app> or www.dda.org.in* upto 16/12/2020 at 03:00 PM (last date of sale) and Opening of technical bid on 17/12/2020 at 03:30 PM. Earnest money amounting to Rs. 10,000/- and shall be deposited through RTGS/NEFT in the account of **“CAU SPORTS DDA (EMD ACCOUNT)”** having account No. **1614159849** with “Kotak Mahindra Bank, Gulmohar Park, New Delhi-110049 (IFSC. **KKBK0000184**). The unique transaction reference of RTGS/NEFT shall have to be uploaded by the quotationer in the E-Tendering system by the prescribed date. The DDOs concern will get earnest money verified from their banks based on the unique transaction reference no. against each RTGS/NEFT payment before the tenders are opened.

Technical Bid (First cover)

The quotations are required to furnish following documents in technical bid:-

- i. Scanned copy of reference of RTGS/NEFT/IMPS (EMD).
- ii. Scanned copy of PAN No.
- iii. Scanned copy of GST Certificate.
- iv. Scanned copy of Experience Completion Certificates as per NIQ condition.
- v. Scanned copy of Turnover of last three consecutive financial year ending March 2019 duly certificate by Chartered Accountant having valid UDIN.
- vi. Scanned copy of Proof of requisite fee deposited with Contractors Registration Board of DDA.

Financial Bid (Second cover)

- (i) Schedule of Financial Bid in the form of BoQ_XXXXX.xls

TERMS & CONDITIONS:-

1. The work/supply shall be done as per specifications.
2. Quoted rate should be inclusive of all taxes / levies including GST, payable under respective states, DDA will not entertain any claim, whatsoever in this regard.
3. The payment will be made after entire satisfaction of Secretary/DSC and AE/RE(Civil)/DSC, DDA.
4. No T & P will be issued by Department.
5. No advance payment will be made to the agency.
6. Commissioner (Sports) reserves the right to accept or reject any bid / quotation without assigning any reason.
7. All material used at Site shall be got approved before supply for design, pattern, colour etc. at site from Secretary/DSC of the concerned DDA Sports Complex.
8. Commissioner (Sports) reserves the right to debar the concerned agency if the work/supply is not completed in stipulated time or supplied item is found to be substandard.
9. Conditional quotation will not be accepted.
10. Necessary statutory deductions as applicable will be made.
11. No minor shall be engaged at site.
12. Nothing extra will be paid to the agency by the department.
13. Validity of Quotation is 60 days from the date of opening.
14. Debarred agency / or individual shall not be permitted to participate in the tendering process. Agency should be reputed and does not have any tarnished reputation.
15. Any individual who has been debarred is not permitted to take part in any negotiations or represent an agency even if he holds a power of attorney on the agencies behalf. Any agency engaging debarred persons is also liable to debarring.
16. The experience of agencies should be taken into account rather than individuals incorporated with the agency, which does not include proprietorship.

17. The quantities of items in schedule are tentative which may change depending upon site conditions and requirements.
18. If the entire work is not done within the stipulated time mentioned in order, it will be sole discretion of the Secretary/DSC to accept the work/supply of item on such terms as the Secretary deemed fit and proper or to cancel the order/ to stop any payment against the work/supply / to forfeit the earnest money or to debar the concerned agency. The decision of the Competent Authority in this behalf shall be final and not to be called in question before any Forum.
19. The contractor will be fully responsible during work/supply. If any loss/ theft/ damage caused at site/ surrounding, the same shall be made good with in quoted rates or recovered from the agency/shall be made good at agency's risk and cost.
20. If any agency submits a faulty or incomplete tender for the first time, 20% of the earnest money so deposited shall be forfeited. However, if the agency commits fault or submits incomplete tender again in the subsequent tenders and the competent Authority finds that the default has been willful, negligent or malafide in its intent, the earnest money shall be forfeited absolutely without assigning any reason and the tenderer shall not be allowed to participate in future tendering.
21. In case the rates quoted by the bidders are same, then in order to arrive at a decision, a draw of lots shall be carried out by a Committee comprising of Secretary/DSC, AAO/DSC and AE/RE/DSC.
22. The experience of agencies should be taken into rather than individuals incorporated with the agency, which does not include proprietorship.
23. Based on real time feedback of members and administrative staff of DDA as and when a deficiency of service is noticed the same will be intimated to the agency/ contractor for rectification. In case there is no improvement/ rectification within prescribed period from the time of intimation proportionate deduction, as approved by the Competent Authority, shall be made from the agency/ contractor.
24. The work/supply shall be completed within 15 days from the date of issue of the Order.
25. Security Deposit @5% shall be deducted from bill which shall be released after three months of completion of work/supply.

Assistant Engineer(Civil)/DDA

N.O.O:-

Copy to :-

1. Commissioner (Sports), DDA-For information please.
2. Director (Sports), DDA-For information please.
3. Director (System)/DDA through E-Mail. ddatender@dda.org.in
4. Sr. A.O. (Sports), DDA.
5. All Secretaries of the DDA Sports Complexes
6. DDA Contractor association E-18 Vikas kuteer, New Delhi
7. DDA Contractor Welfare Association, Room no.12, Barrack no.1, Block-A,Vikas Kuteer, New Delhi.
8. Delhi Contractor Welfare Association (C), 306,Masjid Moth, NDSE, Part-II, New Delhi.
9. AAO / DSC.
10. Notice Board.

Assistant Engineer(Civil)/DDA

Schedule of Quantity

N.O.W:- Maintenance of various Sports Complex/ Golf Course.

S.H.:- Maintenance of old/damaged GI pipe line, repair of broken RR masonry, repair of 2nos screen, plinth protection and other misc work at Dwarka Sports Complex.

S.No.	Description of item	Qty	Unit	Rate	Amount
1	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 50 mm dia nominal bore.	12.30	mtr		
2	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 80 mm dia nominal bore.	31.00	mtr		
3	Providing and filling sand of grading zone V or coarser grade, allround the G.I. pipes in external work : 50 mm diameter pipe.	12.30	mtr		
4	Providing and filling sand of grading zone V or coarser grade, allround the G.I. pipes in external work : 80 mm diameter pipe	31.00	mtr		
5	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws, including excavation, refilling the earth or cutting of wall and making good the same complete wherever required : 50 mm nominal bore.	3.00	Each		
6	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws, including excavation,refilling the earth or cutting of wall and making good the same complete wherever required : 80 mm nominal bore	3.00	Each		
7	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation leveling and dressing and finishing the top smooth.	40.68	Sqm		
8	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge : In cement mortar .	5.70	Cum		
9	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand).	5.70	Cum		
10	Welding by gas or electric plant including transportation of plant at site etc. complete.	1191.00	cm		
11	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	166.08	Kg		
12	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :One or more coats on old work.	104.03	Sqm		
13	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	94.31	Cum		

14	Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge (Door handle, lock and stopper etc. to be paid separately).	2.32	Sqm		
15	Providing and Fixing 15 mm thick densified tegular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture of size 595 x 595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanising @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre, and cross "T" of size 24x28 mm made out of 0.33 mm (Minimum) sheet, 1200 mm long spaced between main'T' at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross 'T' of length 600 mm and size 24 x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm panel to from grid of size 600x600 mm, resting on periphery walls /partitions on a Perimeter wall angle pre-coated steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long dry wall screws @ 230 mm interval and laying 15 mm thick densified edges calicum silicate ceiling tiles of approved texture in the grid, including, cutting/ making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required. Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25x35x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm G.I. adjustable rods with galvanised steel level clips of size 85 x 30 x 0.8 mm, spaced at 1200 mm centre to centre along main 'T', bottom exposed with 24 mm of all Tsections shall be pre-painted with polyster baked paint, for all heights, as per specifications, drawings and as directed by Engineer-in-Charge. Note :- Only calcium silicate false ceiling area will be measured from wall to wall. No deduction shall be made for exposed frames/ opening (cut outs) having area less than 0.30 sqm.The calcium silicate ceiling tile shall have NRC value of 0.50 (Minimum), light reflection > 85%, non- combustible as per B.S. 476 part IV, 100% humidity resistance and also having thermal conductivity <0.043 w/ mK.	10.17	sqm		
16	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)	126.00	sqm		
Total (Rs.)					