

दिल्ली विकास प्राधिकरण
राष्ट्रमण्डल खेल खण्ड-1
स्कूल ब्लॉक, शकरपुर दिल्ली-92

सं। एफ 5 (327) 2020-21/ईई/सीजीडी .1/ए/ डीडीए /695

दिनांक: 06-03-2021

सेवा मे

श्री अली ओसामा
डी-15/1, ग्राउण्ड फ्लोर
ओखला विहार, जामिया नगर
नई दिल्ली-110025

कार्य का नाम : सीडब्ल्यूजी के तहत पूर्ण योजना का रखरखाव।

उप प्रमुख : गेट नंबर -3 और फुटपाथ के पास मौजूदा सीमा की दीवार का सुधार का कार्य।

एनआईटी नंबर: 05 / ईई / सीजीडी -1 / डीडीए / 2020-2021।

- संदर्भ:
- कार्य स्वीकृत पत्र की गारंटी आकार में प्रस्तुत एफडीआर असर सं-397600 कस्टमर आई.डी. सं. C00398091 दिनांक : 04.03.2021 रु .19500/- की राशि पंजाब नेशनल बैंक, सरिता विहार नई दिल्ली-110076 द्वारा जारी ।
 - पत्र के आशय संख्या F.5(327)2020-21/EE/CGD.1/A/DDA/673 दिनांक 20/02/2021.

श्रीमान,

उपरोक्त वर्णित कार्य के लिए आपकी प्रतिशत दर की निविदा दिल्ली विकास प्राधिकरण की ओर से आपके सहमत दरों पर नीचे विवरण अनुसार स्वीकार की गई है: -

- अनुमानित लागत : रु. 12,94,966 / - (बारह लाख चौरानवे हजार नौ सौ छयासठ)
- उद्धत और स्वीकृत दर : @50.11% नीचे (पचास दशमलव ग्यारह प्रतिशत नीचे)
अनुमानित लागत से डी.एस.आर. 2018 पर।
- उद्धत एवं स्वीकृत निविदा राशि : रु. 6,46,059 / - (छह लाख छियालीस हजार उनसठ)।
(संलग्न परिशिष्ट की अनुसूची के अनुसार)।

आपसे अनुरोध है कि इस पत्र के जारी होने की तारीख से 15 दिनों के भीतर औपचारिक समझौते को पूरा करने के लिए 100/- (केवल एक सौ रुपये) के मूल्य वाले गैर-न्यायिक स्टाम्प पेपर के साथ इस कार्यालय में उपस्थित हों।

आपसे निवेदन है कि काम शुरू करने के लिए आप इस डिवीजन के सहायक इंजीनियर -2 से सम्पर्क करें। कृपया ध्यान दें कि कार्य शुरू करने की तारीख अनुमति पत्र जारी करने की तारीख के 10 वें दिन के बाद होगी।

कार्य के निष्पादन के लिए अनुमत समय केवल 45 (पैंतालिस दिन) होगा।

धन्यवाद,

आपका आभारी,

संलग्न: मात्रा की अनुसूची

हस्ता / -
(राजीव कुं शर्मा)
अधिसासी अभियंता
रा.म.खेल खण्ड-1 / दि.वि.प्रा.

OFFICE OF THE EXECUTIVE ENGINEER
COMMONWEALTH GAMES DIVISION NO.1
D.D.A., SCHOOL BLOCK, SHAKARPUR
DELHI -110 092

No. F.5 (327)2020-2021/EE/CGD-1/A/DDA 695

Dated: 6-3-2021

To,
Sh. Ali Osama
D-15/1, Ground Floor
Okhla Vihar, Jamia Nagar
New Delhi-110025

Name of work: M/O Completed Scheme under CWG.
Sub Head: Improvement of existing boundary wall near Gate No. -3 and footpath.
NIT No. : 05/EE/CGD-1/DDA/2020-2021.
Reference: 1. Performance Guarantee submitted in shape FDR Sl. No. 397600 /
Customer ID No.C00398091 dt. 04/03/2021 amounting to
Rs.19500/- of Punjab National Bank, Sarita Vihar, New Delhi-110076.
2. Letter of Intent No F.5 (327) 2020-2021/EE/CGD.1/A/DDA/673 dated
20/02/2021.

Dear Sir(s),

Your percentage rate tender for the above mentioned work has been accepted on behalf of Delhi Development Authority at your tendered tender rates as per detail given below:-

1. Estimated cost : Rs.12,94,966/- (Rupees Twelve lakh ninety four thousand nine hundred sixty six only).
2. Quoted and accepted : @50.11% below (Fifty point eleven percent below)
Rate the estimated cost on DSR 2018.
3. Quoted and Accepted :
Tender amount : Rs.6,46,059/- (Rupees Six lakh forty six thousand and fifty nine only).
As per Annexure Schedule of Quantity enclosed).

You are requested to attend this office along with a non-judicial stamp paper worth Rs.100/- (Rupees one hundred only) to complete formal Agreement within 15 days from the date of issue of this letter.


You are requested to contact Asstt. Engineer-2 of this Division and to start the work at once. Please note that the time allowed for carrying out the work as entered in the tender shall be reckoned 10th day after the date of issue of letter of award to commence the work.

The time allowed for execution of the work will be 45 (Forty five) days only.

Thanking You,


Encl.: Annexure Schedule of quantity

Yours faithfully,


(Rajeev Kr. Sharma)
Executive Engineer
C.G.D.1/D.D.A.

Copy to:-

1. Chief Engineer/EZ/ DDA.
2. S.E./Eastern Civil Circle-2 /DDA.
3. Director (System), DDA through E-Mail ddatender@dda.org.in for hosting the award letter on DDA's website www.dda.org.in .
4. Secy. (CRB), DDA.
5. Dy. CAO/CAU/EZ/DDA.
6. All Executive Engineers, Eastern Maintenance Divisions & Commonwealth Games Divisions-3 & 4, DDA.
7. Labour Commissioner, 5, Sham Nath Marg, Delhi-54 for information please.
8. EE (QAC) I, DDA.
9. Income Tax Officer (Contractor Circle), 21st Floor, Civic Centre, Minto Road, New Delhi-110002.
10. Sales Tax Officer (Work Contract Cell), Ward No.4, Bikri Kar Bhawan, ITO, New Delhi.
11. Sr. A.O. (Works)-I/DDA.
12. F.O. to C.E. /East Zone/ D.D.A.
13. Sr. A.O./CAU/EZ/DDA.
14. A.E.-2, CGD.1, D.D.A. along with a copy of Annexure Schedule of Quantity with the following direction:-
 - a) To get relevant register from CB/CGD-1/DDA under the signature of undersigned.
 - b) Test check/record of measurement on all important/hidden items is to be done by AE to the extent of 100%.
15. A.E. (P)/CGD.1/DDA.
16. A.S.O., C.G.D.1, D.D.A.
17. Copy to agreement and all concerned files.


Executive Engineer
C.G.D.-1/D.D.A.

ANNEXURE
SCHEDULE OF QUANTITIES


Name of work: M/O Completed Scheme under CWG.
Sub Head: Improvement of existing boundary wall near Gate No. -3 and footpath.
NIT No. : **05/EE/CGD-1/DDA/2020-2021.**

Sl. No.	Item Description	Quantity	Units	Rate in		AMOUNT in	
				Rs.	P.	Rs.	P.
1.00	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm.	244.12	sqm.	54.85		13390.00	
2.00	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil.	32.55	cum.	181.85		5919.00	
3.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources: 8 graded stone aggregate 40 mm nominal size derived from natural sources).	16.89	cum.	5789.60		97786.00	
4.00	Providing and fixing pre-polished precast concrete designer tile 20mm/25mm thick extra heavy duty of approved brand and manufacture (ultra tile or equivalent) and of required shape, size and deisgn over a bed of 20mm thick average cement mortar 1:4 (1 cement : 4 coarse sand) joined with neat cement slurry including pointing the joints with ready mixed pointing material complete in all respect as manufacturers specifications and direction of Engineer-in-charge.	244.12	sqm.	1334.75		325839.00	
5.00	Taking out existing kerb stones of all types from footpath/ central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	115.00	mtr.	28.05		3226.00	

6.00	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	4.32	cum.	8376.15	36185.00
7.00	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 300 mm dia. R.C.C. pipe	18.00	Mtr.	863.65	15546.00
8.00	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) up to haunches of S.W. pipes including bed concrete as per standard design : 300 mm diameter S.W. pipe	18.00	Mtr.	993.65	17886.00
9.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources).	5.39	cum.	6788.60	36591.00
10.00	Neat cement punning.	84.51	Sqm.	62.75	5303.00
11.00	Providing and fixing in position precast RCC horizontal grating with frame complete of size 500 × 450 mm as per standard design.	5.00	nos.	1709.80	8549.00
12.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 fine sand) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources).	1.62	cum.	5225.15	8465.00

13.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	17.80	cum.	6376.25	113497.00
14.00	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	133.74	Sqm.	39.00	5216.00
15.00	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	189.54	Sqm.	263.55	49953.00
16.00	15 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	54.00	sqm.	303.90	16411.00
17.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	892.32	Kg.	131.00	116894.00
18.00	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 25x25 mm made of G.I. wire of dia 3 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge.	47.52	Sqm.	909.60	43224.00
19.00	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately).	36.00	mtr.	290.80	10469.00
20.00	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	243.54	sqm.	91.25	22223.00

21.00	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litres/10 sqm complete including cost of Priming coat.	2970.35	sqm.	87.20	259015.00
22.00	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work.	93.50	sqm.	121.55	11365.00
23.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: One or more coats on old work.	900.74	Sqm.	79.95	72014.00
Total in Figures					1294966.00
Quoted and accepted Rate in Figures			Less (-)	@50.11% Below	(-) 648907.00
Quoted and accepted tender amount in Figures					646059.00
Quoted and accepted tender amount Words		Rupees Six Lakh Forty Six Thousand & Fifty Nine Only			


 (Rajeev Kr. Sharma)
 Executive Engineer
 CGD-1/DDA