



दिल्ली विकास प्राधिकरण
DELHI DEVELOPMENT AUTHORITY
उप-निदेशक कार्यालय, उद्यान खण्ड - तृतीय
OFFICE OF DY. DIR. HORT. DIV. NO. III
बी2बी, जनकपुरी, नई दिल्ली-110058
B2B, JANAKPURI, NEW DELHI: 58



No. F54 (58) DD/Hort.-III/2020-21/DDA/ 45

Dated: 15/11/2021

To

M/s Mahesh Chand Gupta,
D-6/360, First Floor, Sec-6, Rohini,
Delhi- 110085.

Name of work: M/o Completed scheme of N/A-II under SWZ.

M/o Distt. Park along with NG Drain Opp. BG-6 Paschim Vihar.

Sub Head: S/S of Good earth, WDCM, Jamuna sand, Digging of holes, S/o Plants, Neem coated urea etc. at site.

PG Ref.: FDR/Bank Guarantee/Account No. 50300478943252 dated 03.12.2020 Amount Rs. 13,700/-from HDFC Bank Ltd., Garg Plaza, Sector-8, Rohini, Delhi-110085.

Sir,

Your quoted item rates tenders for the above mentioned work has been accepted on behalf of DDA as under:

Estimated cost	:	Rs. 3,49,193.00
Contractor quoted Amount	:	Rs. 2,72,350.00
Accepted tendered Amount	:	Rs. 2,72,350.00 (Rupees Two Lakh Seventy Two Thousand Three Hundred Fifty Only).
Percentage of tender	:	22.00% below.
Time Allowed	:	60 Days.

The percentage to be taken for the purpose of clause-12 shall be 22.00% below on rates based on DSR-2018. You are requested to attend the office to sign the agreement along with non-judicial stamp paper worth Rs.50/- within ten (10) days from the date of issue of this letter, failing, which the acceptance of tender is likely to be withdrawn and the earnest money forfeited. You are therefore, directed to contact the A.D. - II of this office and start the work at once. Please note that the time allowed for carrying out the work as entered in the tender still be reckoned after the ten days from the date of issue of this letter to commence the work. Your letter dated 18-12-2020 shall be part of the Agreement.

Dy. Director (Hort.) - III/DDA

Copy to:

1. Director (Hort.) NW, DDA.
2. Dy. Director (QC) III, DDA.
3. A.O. (W) II, DDA.
4. A.O. (CAU) Dwarka, DDA.
5. Dy. Dir. Hort. II, V and Dwarka, DDA.
6. Income Tax Commr. W No. _____ New. Delhi.
7. A.D.-II, Hort. Div.- III, DDA.
8. Comm. Sale Tax. NCT Delhi.
9. File Concern.
10. Agreement File.
11. DDA website <https://eprocure.gov.in/eprocure/app> or www.dda.org.in or cPPP-nic@nic.in

Dy. Director (Hort.) - III/DDA



दिल्ली विकास प्राधिकरण
उप-निदेशक कार्यालय, उद्यान खण्ड - तृतीय
बी2बी, जनकपुरी, नई दिल्ली-110058



AWARD SCHEDULE

Name of Work: M/o Completed scheme of N/A-II under SWZ.

M/o Distt. Park along with NG Drain Opp. BG-6 Paschim Vihar.


S.H: S/S of Good earth, WDCM, Jamuna sand, Digging of holes, S/o Plants, Neem coated urea etc. at site.

NIT No. 57/DD/Hort.-III/DDA/2020-21

S. No.	Description of Work / Item(s)	Quantity	Units	M/s Mahesh Chand Gupta	
				Rate	Amount
1	Supply and stacking of good earth at site by including mechanical transport royalty and carriage, loading unloading with all lead and lift. (Good Earth measured in stacks will be reduced for 20% payment)	16.00	Cum	300.00	4800.00
2	Supply and Stacking of well decayed cattle manure at site by including mechanical transport royalty and carriage and loading, unloading for all lead and lift at site. (Cattle manure measured in stacks will be reduced by 8 %for payment)	54.00	Cum	200.00	10800.00
3	Supply and stacking of Jamuna Sand at site by including mechanical transport, royalty carriage and loading unloading for all lead and lift.	16.00	Cum	500.00	8000.00
4	Supply and Stacking of Red Bajri at site by mechanical transport i/c royalty and carriage loading, unloading with all lead and lifts.	8.00	Cum	800.00	6400.00
5	Earth work in excavation by mechanical means (Hydraulic Excavator)/manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10sqm on plan) including disposal of excavated earth lead up to 50m and lift up to 1.5m, as per direction of engineer-in-charge. 5 mtr. X 3 mtr. X 2 mtr. X 5 Nos.= 150 Cum	150.00	Cum	150.00	22500.00
6	Supply of Chemical fertilizer Neem coated urea in 45 kg packing at site.	5.00	Bag	500.00	2500.00
7	Supply of Chlorpyriphos 20% E.C (ISI) as per specification at site (Packing in one Ltr.)	10.00	Ltr.	100.00	1000.00
8	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ration of 2:1 by volume (2 part of stacked volume of earth after reduction by 20% : 1 part of stacked volume of manure after reduction by 8%) flooding with water dressing including removal of rubbish and surplus earth . If any, with all leads and lift (cost of manure. sludge or extra good earth if needed to paid for separately).				
8.1	Holes 0.90 m. dia and 0.90 m. deep	50.00	Each	120.00	6000.00
8.2	Holes 0.60 m. dia and 0.60 m. deep	100.00	Each	40.00	4000.00
8.3	Holes 0.45 m. dia and 0.45 m. deep	1000.00	Each	15.00	15000.00
9	Supply of Tree Plant:				
9.1	Providing and stacking of Bauhinia purpurea (Kachnar) of height 150-165 cm. in big poly bags of size 25 cm as per direction of the officer-in-charge.	50.00	Each	75.00	3750.00
9.2	Providing and stacking of Ficus shiela of height 150-165 cm. in big poly bags of size 25 cm as per direction of the officer-in-charge.	50.00	Each	50.00	2500.00
10	Supply of Shrub Plant:				
10.1	Providing and stacking of Bougainvillea (Variety Butiana, Lady Mary Baring, Mahara,Mohan,Scarlet Queen, Variegated, Glabra Formosa, Peruviana Odissi, Paratha, Subhra,Thimma, Spectabilis L.N Birla, Refulgens) of height 30 cm. to 45 cm. with 2-3 branches in 20 cm size of Earthen pots / Plastic pots & as per direction of the officer-in-charge.	100.00	Each	40.00	4000.00
10.2	Providing and stacking of Thevetia nerifolia of height 60-75 cm. with 5-6 branches in poly bags of size 25 cm as per direction of the officer-in-charge.	100.00	Each	10.00	1000.00

	Supply of Hedge Plant:				
	Providing and stacking of Putranjiva roxburghii of ht. 45-60 cm in bag of size 15 cm as per direction of the officer-in-charge.	750.00	Each	10.00	7500.00
11.2	Providing and stacking of Clerodendrum inerme having ht. 25 cm to 30 cm multi branched in 20 cm size of Earthen Pot/Plastic Pot & as per direction of the officer-in-charge.	1000.00	Each	10.00	10000.00
12	Supply of Ground Cover:				
12.1	Providing and stacking of Alternanthera species of height 15 cm to 20 cm, full of branches and foliage in 15 cm size of Earthen Pot/Plastic Pot & as per direction of the officer-in-charge.	500.00	Each	10.00	5000.00
12.2	Providing and stacking of Wedelia trilobata, full of leaves in 15 cm size of Poly bags & as per direction of the officer-in-charge.	1500.00	Each	10.00	15000.00
13	Engaging of J.C.B./Hydraulic excavator (3-D) with driver, fuel and helper etc. for cleaning of wild growth, removal of building rubbish, debris industrial waste and refuse etc. as per direction of Engineer-in-charge.	8.00	P/Day	6500.00	52000.00
14	Supply of R.H. Pipe (ISI Mark is 444 type -II 25 mm dia) working pressure 10.2 F/Cm/2 at site.	200.00	meter	80.00	16000.00
15	Supply of PVC Pipe (Delivery Hose) 3" dia should have working pressure of 5kg/Sqcm at site.	150.00	meter	90.00	13500.00
16	Provision of Cycle Rickshaw fitted with moter cycle tyre tube 28x11 with wooden trolley 36" x 48" x 15" with Neelam or equivalent kit made of 30 mm wooden plank supported with M.S. angle of same welded cicres frame to be linked in side with 25 guage, M.S. sheet and internal side complete in all respect.	1.00	Each	9100.00	9100.00
17	Petrol Driven Brush Cutter/Bush Cutter/Weed Cutter of STIHL Germany model No. FS 400 with engine displacement of 40.2 CC with the rated power output of 1.9 Kw/2.6hp dry weight 8.0 kg. overall length without cutting tool 1.77 mtrs. Tank capacity 0.67 Ltrs anti vibration engine, elasto start, multi function bike handle along with std tools & accessories.	1.00	Each	35000.00	35000.00
18	Nylon Line 3mm square shape for Brush Cutter of STIHL Germany make well packed in the Blister packing of 56 mtr yellow in colour.	200.00	meter	10.00	2000.00
19	Provision of Galvanised steel Barbed Wire	3.00	qtl.	5000.00	15000.00
Total ₹ 2,72,350.00					

Rupees Two Lakh SeventyTwo Thousand Three Hundred Fifty Only


 Dy. Director (Hort.)
 Hort. Div.- III/DDA



दिल्ली विकास प्राधिकरण
उप-निदेशक कार्यालय, उद्यान खण्ड - तृतीय
बी2बी, जनकपुरी, नई दिल्ली-110058

Term & Conditions

Name of work: M/o complete scheme of N/A – II under SWZ.

M/o Distt. Park along with NG Drain Opp. BG-6 Paschim Vihar.

Sub Head: S/S of Good earth, WDCM, Jamuna sand, Digging of holes, S/o Plants, Neem coated urea etc. at site.

1. The work shall be executed as per CPWD specifications.
2. No T & P shall be issued by the department, all the arrangement for T & P shall be arranged by the contractor at his own.
3. The rates should be quoted in both figure and words including all taxes.
4. The undersigned reserves the right to reject all or the lowest rate tender without assigning any reason.
5. All labour liabilities will be beard by the contractor during execution period, DDA will not have any responsibilities of the deployed labour.
6. DDA is not responsible for any litigation with labour in Court of Law & contractor will settle the matter on his own risk & cost.
7. DDA will not pay any compensation to the labour of any miss-happening occurred during the execution of work.
8. If any material is rejected or work found defective, the same shall be removed/rectified by the contractor within one week failing which the same shall be removed/rectified by the department & cost will be recovered from the agency as approved by the Competent Authority.
9. The quantity can be increased or decreased as per actual requirement at site.
10. No manpower shall be engaged by the agency below 18 year or above 60 years in age.
11. The instructions of the department staff are to be carried over properly, in case of any difference of opinion/interpretation of specification and condition the matter is to be referred by the contractor to the Officer-in-charge for his decision with shall be final and binding.
12. All incident charge of any kind whatsoever including cartage, storage, cutting and wastage etc. shall be born exclusively by the contractor and no claim to be entertained to this effect.
13. The contractor must be available at site of work whenever Officer-in-charge will visit the site.
14. The work should be completed within stipulated period.
15. The PH value of good earth and pressure report of R.H. Pipe should be got tested from authorized laboratory on contractor cost.
16. The material like good earth, CDM should be free from kankar-pathar, polythene etc., CDM should be well decomposed.
17. The plants/grass supplied should be in good quality, healthy and free from disease.
18. The contractor/tenderer must be enlisted as Horticulture Category Contractor.
19. The contractor should be supply the total quantity of all items mentioned in schedule of quantity/agreement. If contractor failed to supply the materials as per agreement or as per direction, then the recovery shall be made as per justified rate.


Dy. Director (Hort.)-III/DDA