# द्वारका स्पोर्ट्स कॉम्प्लेक्स

# एनआईक्यू संख्या ०९ / डीएससी / डीडीए / २०१९-२०

सचिव, द्वारका स्पोर्ट्स कॉम्प्लेक्स, दिल्ली विकास प्राधिकरण, निम्नलिखित कार्य के लिए अनुभवी एजेंसियों से ऑनलाइन निविदाए आमंत्रित की जाती है। ऑनलाइन निविदाए 13.01.2020 को दोपहर 3.00 बजे तक भेजी जा सकती है। जो 15.01.2020 को सुबह 11.00 बजे सिरी फोर्ट स्पोर्ट्स कॉम्प्लेक्स खोली जाएँगी। निविदा के नियम एवं शर्तों तथा मदो का विवरण अगले प्रष्ट पर दिया है जो https://eprocure.gov.in/eprocure/app की वेबसाइट से भी प्राप्त की जा सकती है

स.	विवरण	अनुमानित मूल्य	धरोहर राशि	अवधि
	कार्य का नाम :द्वारका स्पोर्ट्स कॉम्प्लेक्स			
1	का रखरखाव ।	Da 2 27 204/	Da 10.000/	15 दिन
	उप नाम : द्वारका स्पोर्ट्स कॉम्प्लेक्स में	Rs. 2,37,304/-	Rs. 10,000/-	१५ ।दन
	विविध सिविल मरम्मत कार्य।			

स्थानिक अभियन्ता, दि.वि.प्रा.

सं. फ. F14 (30) / डीएससी / डीडीए /C/ 2019-20/11

दि. 04/01/2020

## <u>प्रति:</u>

- 1. आयुक्त (खेल), दि.वि.प्रा.
- 2. निदेशक (सिस्टम), दि.वि.प्रा. वेबसाइट के प्रकाशन के लिए ईमेल के माध्यम से।
- 3. सचिव (समन्वय), सि.फो.खे.प.
- 4. दि.वि.प्रा. खेल परिसर के सभी सचिव अपने संबंधित परिसरों के सूचना बोर्ड पर निविदा आमंत्रण सूचना प्रदर्शित करने के अनुरोध के साथ।
- 5. सचिव / दि.वि.प्रा. ठेकेदार कल्याण संघ, बैरक नंबर 1, ब्लॉक-ए, विकास कुटीर, नई दिल्ली
- 6. महासचिव, दिल्ली ठेकेदार कल्याण संघ (रजि।), 306, मस्जिद मोठ, एन.डी.एस.ई. भाग- ॥, नई दिल्ली -110004
- 7. सचिव / दि.वि.प्रा. ठेकेदार एसोसिएशन, ई -18, विकास कुटीर, नई दिल्ली।
- 8. ए. ए. ओ.
- 9. ए. ई. (सिविल)
- 10. सूचना बोर्ड

स्थानिक अभियन्ता दि.वि.प्रा.

# DELHI DEVELOPMENT AUTHORITY Dwarka Sports Complex Sector-11, Dwarka, New Delhi-110075

No. F14(30)DSC/DDA/2019-20/ 11

#### Notice Inviting Quotation No.09/DSC/DDA/2019-20

Dated: 04/01/2020

Online quotations are invited on behalf of Delhi Development Authority, (Sports Wing) for the following works at Dwarka Sports Complex. The quotation shall be uploaded in two parts, namely, 'Part -I' containing Technical Bid and 'Part - II' comprising 'Financial Bid'. The bid not uploaded in accordance with the prescribed manner will not be accounted for at all. Only those agencies/ Firm/ Person have completed similar nature of work (Three or more similar nature works each costing not less than 40% of the estimated cost put to quotation, or two similar works costing each not less than 60% of the estimated cost put to quotation, or one similar works costing not less than 80% of estimated cost put to quotation) during the last seven years in Government Department or Public Sector undertaking with annual turnover more than 30% of the estimated cost in each year during the immediate last three consecutive financial year ending March 2019 duly certified by Chartered Accountant are entitled to apply. A proof thereof should be upload with the Technical Bid. The quotationer should be registered with the Department of GST and furnish a copy of registration with the quotation.

Name of work: - Maintenance of Various Sports Complex/ Golf Courses (M/o DSC).

SH: - Miscellaneous civil repair work at Dwarka Sports Complex.

Estimated cost: Rs. 2,37,304/- Earnest money-Rs. 10,000/-

#### (SCHEDULE OF QUANTITY ATTACHED)

Quotation documents can be obtained / download on the e-tendering portal i.e. website <a href="https://eprocure.gov.in/eprocure/app">https://eprocure.gov.in/eprocure/app</a> or <a href="www.dda.org.in">www.dda.org.in</a> upto <a href="13/01/2020">13/01/2020</a> (last date of sale) and Opening of technical bid on <a href="15/01/2020">15/01/2020</a>. Earnest money amounting to <a href="Rs. 10,000/">Rs. 10,000/-</a> and shall be deposited through RTGS/NEFT in the account of <a href="#">"CAU SPORTS DDA (EMD ACCOUNT)"</a> having account No. <a href="1614159849">1614159849</a> with "Kotak Mahindra Bank, Gulmohar Park, New Delhi-110049 (IFSC. KKBK0000184). The unique transaction reference of RTGS/NEFT shall have to be uploaded by the quotationer in the E-Tendering system by the prescribed date. The DDOs concern will get earnest money verified from their banks based on the unique transaction reference no. against each RTGS/NEFT payment before the tenders are opened."

#### Technical Bid (First cover)

The quotations are required to furnish following documents in technical bid:-

- i. Scanned copy of reference of RTGS/NEFT/IMPS (EMD).
- ii. Scanned copy of PAN No.
- iii. Scanned copy of GST Certificate.
- iv. Scanned copy of Experience Completion Certificates as per NIQ condition.
- Scanned copy of Turnover of last three consecutive financial year ending March 2019 duly certificate by Chartered Accountant having valid UDIN.
- vi. Scanned copy of Proof of requisite fee deposited with Contractors Registration Board of DDA.

#### Financial Bid (Second cover)

(i) Schedule of Financial Bid in the form of BoQ\_XXXXX.xls

#### **TERMS & CONDITIONS:-**

- 1. The work/supply shall be done as per specifications.
- Quoted rate should be inclusive of all taxes / levies including GST, payable under respective states, DDA will not entertain any claim, whatsoever in this regard.
- 3. The payment will be made after entire satisfaction of Secretary/DSC and AE/RE(Civil)/DSC, DDA.
- 4. No T & P will be issued by Department.
- 5. No advance payment will be made to the agency.

- Commissioner (Sports) reserves the right to accept or reject any bid / quotation without assigning any reason.
- 7. All material used at Site shall be got approved before supply for design, pattern, colour etc. at site from Secretary/DSC of the concerned DDA Sports Complex.
- 8. Commissioner (Sports) reserves the right to debar the concerned agency if the work/supply is not completed in stipulated time or supplied item is found to be substandard.
- 9. Conditional quotation will not be accepted.
- 10. Necessary statutory deductions as applicable will be made.
- 11. No minor shall be engaged at site.
- 12. Nothing extra will be paid to the agency by the department.
- 13. Validity of Quotation is 60 days from the date of opening.
- 14. Debarred agency / or individual shall not be permitted to participate in the tendering process. Agency should be reputed and does not have any tarnished reputation.
- 15. Any individual who has been debarred is not permitted to take part in any negotiations or represent an agency even if he holds a power of attorney on the agencies behalf. Any agency engaging debarred persons is also liable to debarring.
- 16. The experience of agencies should be taken into account rather than individuals incorporated with the agency, which does not include proprietorship.
- 17. The quantities of items in schedule are tentative which may change depending upon site conditions and requirements.
- 18. If the entire work is not done within the stipulated time mentioned in order, it will be sole discretion of the Secretary/DSC to accept the work/supply of item on such terms as the Secretary deemed fit and proper or to cancel the order/ to stop any payment against the work/supply / to forfeit the earnest money or to debar the concerned agency. The decision of the Competent Authority in this behalf shall be final and not to be called in question before any Forum.
- 19. The contractor will be fully responsible during work/supply. If any loss/ theft/ damage caused at site/ surrounding, the same shall be made good with in quoted rates or recovered from the agency/shall be made good at agency's risk and cost.
- 20. If any agency submits a faulty or incomplete tender for the first time, 20% of the earnest money so deposited shall be forfeited. However, if the agency commits fault or submits incomplete tender again in the subsequent tenders and the competent Authority finds that the default has been willful, negligent or malafide in its intent, the earnest money shall be forfeited absolutely without assigning any reason and the tenderer shall not be allowed to participate in future tendering.
- 21. In case the rates quoted by the bidders are same, then in order to arrive at a decision, a draw of lots shall be carried out by a Committee comprising of Secretary/DSC, AAO/DSC and RE/DSC.
- 22. The experience of agencies should be taken into rather than individuals incorporated with the agency, which does not include proprietorship.
- 23. Based on real time feedback of members and administrative staff of DDA as and when a deficiency of service is noticed the same will be intimated to the agency/ contractor for rectification. In case there is no improvement/ rectification within prescribed period from the time of intimation proportionate deduction, as approved by the Competent Authority, shall be made from the agency/ contractor.
- 24. The work/supply shall be completed within 15 days from the date of issue of the Order.
- 25. Security Deposit @5% shall be deducted from bill which shall be released after three months of completion of work/supply.

Assistant Engineer(Civil)/DDA

#### N.O.O:-

### Copy to :-

- 1. Commissioner (Sports), DDA-For information please.
- 2. Director (System)/DDA through E-Mail. ddatender@dda.org.in

- 3. Sr. A.O. (Sports), DDA.
- 4. All Secretaries of the DDA Sports Complexes
- 5. DDA Contractor association E-18 Vikas kuteer, New Delhi
- 6. DDA Contractor Welfare Association, Room no.12, Barrack no.1, Block-A, Vikas Kuteer, New Delhi.
- 7. Delhi Contractor Welfare Association (C), 306, Masjid Moth, NDSE, Part-II, New Delhi.
- 8. AAO / DSC.
- 9. Notice Board.

Assistant Engineer(Civil)/DDA

## Schedule of Qty

N.O.W:- Maintenance of various Sports Complex/ Golf Course. S.H.: Misc. civil repair work at Dwarka Sports Complex.

S.No.	Description of item	Qty	Unit	Rate	Amount
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead.	38.10	sqm		
2	12 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand)	38.10	sqm		
3	Demolishing brick tile covering in terracing including stacking of serviceable material and disposal of unserviceable material within 50 meters lead.	11.49	sqm		
4	Demolishing mud phaska in terracing and disposal of material within 50 meters lead.	1.73	Cum		
5	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: (a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment. (b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over 20 mm thick layer of cement mortar of mix 1:5 (1 cement :5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs. (c) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/ sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer- in-charge. (d) Finishing the surface with 20 mm thick joint less cement mortar of mix 1:4 (1 cement:4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer- in-charge including laying glass fiber cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3 mm deep. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test. All above operations to be done in order and as directed and specified by the Engineer-in-Charge :With average thickness of 120 mm and minimum thickness at khurra as 65 mm.	12.81	sqm		
6	Making alignments of existing aluminum doors to make them in proper working condition including changing all necessary fixtures and fitting like handle, tower bolt etc. as required and as per instructions from Engineer-in-charge.	3.00	Each		

	Dismantling tile work in floors and roofs laid in cement mortar			
7	including stacking material within 50 meters lead.a) For thickness of tiles 10 mm to 25 mm	19.58	sqm	
8	Providing and fixing 1st quality ceramic glazed wall tiles conforming to 1S: 15622 (thickness to be specified by the manufacturer), of approved make, in all colors, shades except burgundy, bottle green, black of any size as approved by Engineer- in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	16.54	sqm	
9	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS: 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.	3.04	sqm	
10	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	314.99	sqm	
11	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications: Two or more coats applied on walls @ 1.25 ltr/10 sqm. over and including one coat of Special primer applied @ 0.75 ltr / 10sqm	314.99	sqm	
12	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: One or more coats on old work.	20.55	sqm	
13	Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & double action hydraulic floor spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-incharge (Door handle, lock and stopper etc.to be paid separately).	5.50	sqm	
14	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of ail dirt, scales, oil, grease and other foreign material etc. and lining out complete.	51.91	sqm	
15	Providing and fixing stone slab with table rubbed, edges rounded and polished, of size 75x50 cm deep and 1.8 cm thick, fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6 mm nominal size) as per direction of Engineer-in-charge and finished smooth. Granite Stone of approved shade	0.54	sqm	

16	Stone tile (polished) work for wall lining over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and cement slurry @ 3.3 kg/sqm including pointing in white cement complete. Granite of any colour and shade	10.12	sqm	
17	Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): Powder coated aluminum (minimum thickness of powder coating 50 micron)	18.10	kg	
17.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	20.48	kg	
18	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade   Type   II, in paneling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer -in- charge. Pre-laminated particle board with decorative lamination on both sides	0.97	sqm	
19	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/ sqm)	2.68	sqm	
20	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS: 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	2.00	Each	
21	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete 125 mm	4.00	Each	
22	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete: 300x10 mm	2.00	Each	

23	Providing & fixing perforated M S sheet for cricket wind screen .	33.22	sqm		
24	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	67.34	sqm		
Total (Rs.)					