

OFFICE OF THE EXECUTIVE ENGINEER
EASTERN DIVISION-3/DDA
POCKET-I, DILSHAD GARDEN, DELHI 110095

Notice Inviting Scaled Quotation

No. F54 (6) EE/ED-3/A/DDA/2019-20/607

Dated: 23.07.2019

The Executive Engineer ED-3 DDA, Pocket-I, Dilshad Garden, Delhi invites on behalf of DDA sealed quotation from specialized agencies, DDA, CPWD & Non-CPWD contractors who possess the necessary eligibility criteria/experience for executing the specialized works for the following work in 3 days of uploading of NIQ on DDA website: www.dda.org.in.

The sealed quotation shall be submitted in the office of EE/ED-3/DDA at Pocket-I, Dilshad Garden, Delhi-110095.

<p>NIQ No. 01/EE/ED-3/DDA/2019-20.</p> <p>Name of Work: - M/o various Scheme under Nazul A/c-II, East Zone.</p> <p>Sub Head: -Desilting/dredging work for Sanjay Lake near DTTDC area at Mayur Vihar Phase-II (Specialized Work).</p> <p>Estimated cost :- Rs. 4,24,126/-</p> <p>Earnest Money NIL, period of completion 30 days.</p>
--

Note: -

1. The sealed quotation shall be received from the specialized agencies who have satisfactorily completed the works as mentioned below during the last 7 years ending previous day of last day of submission of quotation.
2. Three similar works each costing not less than 40% or two works each costing not less than 60% one similar work costing not less than 80% (scanned copy of experience certificate to be uploaded).

Similar Nature of Work: - Desilting/Dredging/Cleaning Work in lakes, ponds, drain, sewer, other alike work.


Ex. Engineer
ED-3/DDA
23/7/19

SCHEDULE OF QUANTITIES

Name of work : M/O various schemes under Nazul Account-II

Sub Head: Desilting/dredging work for Sanjay Lake near DTTDC area at Mayur Vihar Phase II

Item No.	Description	Unit	Quantity	Rate	Amount
2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil.	Cum	1173.11		
2.24.1	Extra rates for quantities of works, executed: In or under water and/or liquid mud, including pumping out water as required (20% of the rate of the item)	Mtr depth	1173.11		
1.1.3	Carriage of materials by Mechanical Transport including loading,unloading - Manure or sludge lead 5 Km	Cum	1173.11		

[Signature]
22/7/19
JE(T)/ED-3

[Signature]
22/7/19
AE(P)/ED-3

[Signature]
22/7/19
EE/ED-3

